





NOTES

- A. A Cowlitz PUD planner must approve trenching and conduit placement in the pedestal.
- B. 2500 lb mule tape must be installed by customer.
- C. The conduit will likely need to be cut off to meet spec.
- D. The PUD will supply the required pedestal and block connectors. Customer must install the pedestal to specifications of this drawing.
- E. The PUD will supply and install conductor from service line to the pedestal and from the pedestal to the meter base.
- F. All conduit and fittings shall be schedule 40 gray electrical PVC.

STANDARDS  PUBLIC UTILITY DISTRICT NO. 1 <small>Cowlitz County, Washington 961 12th Avenue Longview, Washington</small>	INSTALLATION STANDARDS ELECTRICAL SERVICE REQUIREMENTS SECONDARY PEDAESTAL		<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>3/3/25</td> <td>Draft for review</td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REV	DATE	DESCRIPTION	0	3/3/25	Draft for review						
	REV	DATE	DESCRIPTION												
0	3/3/25	Draft for review													
<table border="1"> <tr> <td>Designed</td> <td>Checked</td> <td>Standards Approved</td> <td>Std/Dwg No.</td> </tr> <tr> <td style="text-align: center;">MJD</td> <td style="text-align: center;">DPT</td> <td style="text-align: center;"></td> <td style="text-align: center;">8-30</td> </tr> </table>	Designed	Checked	Standards Approved	Std/Dwg No.	MJD	DPT		8-30							
Designed	Checked	Standards Approved	Std/Dwg No.												
MJD	DPT		8-30												