





NOTES

- A. A Cowlitz PUD planner must approve trenching and conduit placement in the pedestal.
- B. 2500 lb mule tape must be installed by customer.
- C. The conduit will likely need to be cut off to meet spec.
- D. The PUD will supply the required pedestal and block connectors. Customer must install the pedestal to specifications of this drawing.
- E. The PUD will supply and install conductor from service line to the pedestal and from the pedestal to the meter base.
- F. All conduit and fittings shall be schedule 40 gray electrical PVC.

|  <p>PUBLIC UTILITY DISTRICT NO. 1 Cowlitz County, Washington 961 12th Avenue Longview, Washington</p> | <p>INSTALLATION STANDARDS ELECTRICAL SERVICE REQUIREMENTS SECONDARY PEDAESTAL</p> | | <table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>3/3/25</td> <td>Initial release</td> </tr> <tr> <td>1</td> <td>6/18/25</td> <td>90 deg req, renumber</td> </tr> </tbody> </table> | REV | DATE | DESCRIPTION | 0 | 3/3/25 | Initial release | 1 | 6/18/25 | 90 deg req, renumber |
|--|--|---|--|---|------|-------------|------|--------|-----------------|---|---------|----------------------|
| | REV | DATE | DESCRIPTION | | | | | | | | | |
| 0 | 3/3/25 | Initial release | | | | | | | | | | |
| 1 | 6/18/25 | 90 deg req, renumber | | | | | | | | | | |
| <table border="1"> <tr> <td>Designed M. Demos</td> <td>Checked D. Tuominen</td> <td>Standards Approved </td> </tr> </table> | Designed M. Demos | Checked D. Tuominen | Standards Approved  | <table border="1"> <tr> <td>Std/Dwg No.</td> <td style="font-size: 24pt; font-weight: bold;">8-32</td> </tr> </table> | | Std/Dwg No. | 8-32 | | | | | |
| Designed M. Demos | Checked D. Tuominen | Standards Approved  | | | | | | | | | | |
| Std/Dwg No. | 8-32 | | | | | | | | | | | |